LIGHTING FIXTURE SCHEDULE

PROVIDED FOR INFORMATION ONLY.
VERIFY AND INSTALL PER ELECTRICAL DRAWING

03-04-22

ITEM	SYMBOL	DESCRIPTION	QTY.	MFR. & CAT. NO.	REMARK
INTERIOR LIGHTING ITEM					
L1	L1	T-BAR CEILING RECESSED MOUNTED LED LIGHTING FIXTURE, 2' X 4', 120V BAKED-ON WHITE ENAMEL FINISH.	13	LSI FIXTURE: SFP24-LED-FS-UNV-DIM	KITCHEN CEILING LIGHTS, FURNISHED BY OWNER INSTALLED BY GC
L1B	L1B	T-BAR CEILING RECESSED MOUNTED LED LIGHTING EMERGENCY FIXTURE, 2' X 4', 120V BAKED-ON WHITE ENAMEL FINISH.	0	LSI FIXTURE: SFP22-LED-FS-DIM	KITCHEN CEILING LIGHTS, FURNISHED BY OWNER INSTALLED BY GC
L1C	L1C	T-BAR CEILING RECESSED MOUNTED LED LIGHTING FIXTURE, 1' X 4', 120V BAKED-ON WHITE ENAMEL FINISH.	0	LSI FIXTURE: SFP14-LED-FS-UNV-DIM	KITCHEN CEILING LIGHTS, FURNISHED BY OWNER INSTALLED BY GC
L1EM	L1EM	T-BAR CEILING RECESSED MOUNTED LED LIGHTING EMERGENCY FIXTURE, 2' X 4', 120V BAKED-ON WHITE ENAMEL FINISH.	4	LSI FIXTURE: SFP24-LED-FS-UNV-DIM-EM	EMERGENCY KITCHEN CEILING LIGHTS FURNISHED BY OWNER INSTALLED BY GC
L4HO	L4HO	UNIVERSAL MOUNT EXIT SIGN, LED LIGHTED, 120/277V WITH BATTERY PACK, 2 FACE, GREEN LETTER	4	EXITRONIX GVEX-U-BP-WB-BL-R6	EXIT SIGN FURNISHED BY OWNER, INSTALLED BY GC
L6A	L6A	HOOD LIGHT	12	FURNISHED & INSTALLED BY EQUIPMENT SUPPLIER	LIGHTS SUPPLIED & PRE-WIRED BY HOOD VENDOR. ELECTRIC CONTRACTOR TO CONNECT MAIN WIRES TO SHUNT TRIP BREAKER AND HOOD CONTROL PANEL
L6B	L6B	WALK-IN COOLER FLUORESCENT LIGHT, 120 V 48"	3	KASON FIXTURE: # 1181OLCT400 (1)	FURNISHED BY WIC VENDOR, G.R.E. , INSTALLED BY GC
L19	L19	DOWN LIGHT, RECESSED IN CEILING	27	ELITE HOUSING: LD6IC-AT ELITE TRIM: RL631-950L-DIMTR-120-30K-90-RL631-RT-W-WH	FURNISHED BY OWNER, INSTALLED BY GC
L19	L19B	DOWN LIGHT, RECESSED IN CEILING "B" SHALL DESIGNATE BLACK TRIM	9	ELITE HOUSING: LD6IC-AT ELITE TRIM: RL631-950L-DIMTR-120-30K-90-RL631-RT-MB-BK	FURNISHED BY OWNER, INSTALLED BY GC
L19EM	L19EM	EMERGENCY DOWN LIGHT, RECESSED IN CEILING	6	ELITE HOUSING: LD6IC-AT ELITE TRIM: RL631-950L-DIMTR-120-30K-90-RL631-RT-W-WH	EMERGENCY RECESSED DOWN LIGHT - NORMALLY ON INVERTER UNIT - ISOLITE, IMI-12-LC-V1 FURNISHED BY OWNER INSTALLED BY GC
L20	L20W	4" ADJUSTABLE MR16 DOWN LIGHT, RECESSED IN CEILING "W" SHALL DESIGNATE WHITE TRIM	6	ELITE HOUSING: BL4-50-M-120-AT-W ELITE TRIM: B1406-WH	FURNISHED BY OWNER, INSTALLED BY GC
L20	L20B	4" ADJUSTABLE MR16 DOWN LIGHT, RECESSED IN CEILING "B" SHALL DESIGNATE BLACK TRIM	8	ELITE HOUSING: BL4-50-M-120-AT-W ELITE TRIM: B1406-BK	FURNISHED BY OWNER, INSTALLED BY GC
L30	L30	WHITE LED AT DINING ROOM CANOPY	33 L.F.	ZLED FIXTURE: VIL-SIGN-60W-WHT-DC-66MOD-STRING-KIT	FURNISHED BY OWNER, INSTALLED BY GC
L32	L32	WHITE LED AT FIXTURE LOW WALL	23 L.F.	NOVA FLEX - PRO SERIES FIXTURE: NF-CH-3525-2M WHITE	FURNISHED BY OWNER, INSTALLED BY GC
L49	L49	BRONZE SWOOP LIGHT	5	FIXTURE - TBD	DINING AREA - FURNISHED BY OWNER, INSTALLED BY GC
L50R	L50R	12" DIA. PENDANT	3	KAI PENDANT 2 BULB: LED EDISON LAMP.1173467	FURNISHED BY OWNER, INSTALLED BY GC
L100	L100	MICRO INVERTER	1	EVENLITE #PWII12LC (1)	FURNISHED BY OWNER, INSTALLED BY GC
	S	SPEAKER		-	FURNISHED BY MUSIC VENDOR, INSTALLED BY MUSIC VENDOR

NIGHT LIGHTING REQUIREMENTS: "NL" DESIGNATION INDICATED NIGHT LIGHT ON UNSWITCHED CIRCUIT.
1. ONE NL BY SERVICE COUNTER, POS / CASHIER
2. ONE NL BY POS / CASHIER AT DRIVE THRU STATION IF APPLICABLE
3. ONE NL BY EACH EXIT DOORS IN DINNING ROOM & BACK OF HOUSE

ITEM	SYMBOL	DESCRIPTION	QTY.	MFR. & CAT. NO.	REMARK
EXTERIOR LIGHTING					
L40	L40	LINEAR LIGHT AT EXTERIOR STORAGE ROOM	1	COOPER MX-4VT2-LD4-6-DR-UNV-L840-CD1-WL-U	FURNISHED BY OWNER, INSTALLED BY GC
L85	L85	WALL MOUNTED OVER SERVICE DOOR FIXTURE	1	ORACLE: OWP-FC-116-LED-3500L-DIM10-MVOLT-50K-BK	OVER EXTERIOR SERVICE DOOR. REFER ELEVATIONS FOR HEIGHT FURNISHED BY OWNER, INSTALLED BY GC
L86	L86	NAVILITE EMERGENCY LIGHT	4	EXITRONIX MLED1-G-WP	OVER EXTERIOR ENTRANCE & SERVICE DOORS. REFER ELEVATIONS FOR HEIGHT. FURNISHED BY OWNER, INSTALLED BY GC
L86 AEM	L86 AEM	EXTERIOR RECESS EMERGENCY LIGHT	0	ELITE HOUSING: LD6IC-AT LED MODULE: ELITE LED LIGHTING WET LOCATION: RL607-14W-120-FL-30K-SN-SN -WET LOCATION	EMERGENCY RECESSED DOWN LIGHT - NORMALLY ON INVERTER UNIT - ISOLITE, IMI-12-LC-V1 FURNISHED BY OWNER INSTALLED BY GC
L90 BL	L90 BL	DECORATIVE LED WALL SCONCE	4	HINKLEY LIGHTING, ATLANTIS; BLACK; 16495K-LED	AT ENTRY DOORS. REFER ELEVATIONS FOR HEIGHT FURNISHED BY OWNER, INSTALLED BY GC
L91	L91	DECORATIVE LED WALL SCONCE	0	HINKLEY LIGHTING, SILO; BRONZE; 13594AZ-LL; LED	ALONG REAR EIFS BAND FURNISHED BY OWNER, INSTALLED BY GC
L92	L92	WALL MOUNTED OVER SERVICE DOOR FIXTURE	0	LITHONIA LIGHTING WPX1 LED P2 40K MVOLT SDBXD M4	OVER DRIVE THRU AREA SERVICE DOOR FURNISHED BY OWNER, INSTALLED BY GC
L97	L97	LED MOTION SECURITY FLOODLIGHT	3	LITHONIA LIGHTING HGX LED 2RH 40K 120 MO DDB M2	INTERIOR LIGHT SENSOR TO BE WALL MOUNTED AT +142" FURNISHED BY OWNER, INSTALLED BY GC

CEILING SCHEDULE

INSTALLED AND FURNISHED BY. G.C. UNLESS NOTED OTHERWISE

NO	MANUFACTURER	DESCRIPTION	MATERIAL	FINISH
C1	ARMSTRONG	2' X 2' SUSPENDED T-BAR GRID CEILING SYSTEM	OPTIMA 9/16" SQUARE TEGULAR ITEM # 3251	SUSPENSION SYSTEM: 9/16" SUPRAFINE; COLOR: BLIZZARD WHITE CONTACT: SHERRY BRUNT (1-800-442-4212)
C2	USG	2' X 4' SUSPENDED T-BAR GRID CEILING SYSTEM	"VINYL ROCK" VINYL CLAD GYP. BD PANELS	SMOOTH AND WASHABLE WHITE
C3	GOLD BOND	MONOLITHIC CEILING ON METAL FRAMING	5/8" GYP. BD.	SMOOTH PAINT - WHITE AND WASHABLE

SEE SHEET A-103 FOR PAINT SCHEDULE

EQUIPMENT SCHEDULE

03-04-22

PLUMBING
FS INDIRECT CONNECTION TO FLOOR SINK
D DIRECT CONNECTION
RIH ROUGH IN HEIGHT (TO CENTER OF CONNECTION)

ELECTRICAL
D DIRECT CONNECTION
C CONVENIENT OUTLET
FSO FLOOR STUB OUT
DC DROPPED CORD

DESCRIPTION
O OWNER(PANDA EXPRESS, INC.)
GC GENERAL CONTRACTOR
EC ELECTRICAL CONTRACTOR
KEC KITCHEN EQUIPMENT COMPANY
S SERVING AREA
K KITCHEN
(E) EXISTING

SUPPLY BY	GAS K BTU	GAS R.I.H.	GAS SIZE	WASTE TYPE	WASTE SIZE	COLD WATER R.I.H.	COLD WATER SIZE	HOT WATER R.I.H.	HOT WATER SIZE	CONNECTION R.I.H.	CONNECTION TYPE	LOAD WATT	PHASE	H.P.	VOLTS	REMARKS	DIMENSIONS W x D x H (# x H)	MANUFACTURE	MODEL #	EQUIPMENT	NO.
																				SERVING AREA EQUIPMENT	
O																SEE DETAIL	SEE PLAN	KEC	CUSTOM	HOT WELLS COUNTER, SERVICE	1B
O																SEE DETAIL	SEE PLAN	KEC	CUSTOM	SNEEZE GUARD	1S2
O											D	475W	1		120	3 HEATING ELEMENTS	42.375" X 4.25" X 2.375"	GENERAL		43" RADIANT TOP HEATER	1S2b1
O											D	625W	1		120	4 HEATING ELEMENTS	55.375" X 4.25" X 2.625"	GENERAL		56" RADIANT TOP HEATER (2)	1S2b2
O										REF. ELEC.	D	475W	1		120	3 HEATING ELEMENTS	42 1/8"x4.25"x2 5/8"	GENERAL		43" RADIANT TOP HEATER (2)	1S2-S1d
O											D	15A	1		120	SEE DETAIL	SEE PLAN	KEC	CUSTOM	CASHIER & BEVERAGE COUNTER	2Q
O											C	650W	1		120	INDUCTION WARMER	15 3/4" DIA	I/O CONTROLS CORP	ABC-065-14	INDUCTION WELL - 17QT	3F
O											C	650W	1		120	INDUCTION WARMER	12 1/8" DIA	I/O CONTROLS CORP	ABC-065-10	INDUCTION WELL - 11QT	3G
O				FS	3/4"						C	9.3A	1		120	W/LID DISPENSER	30"x30"x35"	CORNELIUS	IDC-255	BEVERAGE DISPENSER	4AB
O										66"	C	7.2A	1		120	ON S/S SHELF	15"x11"X16"	**WELBILT**	**16-2172**	BOOSTER	4B
O																	40"x18"	**WELBILT**	**15-2903-IP**	SODA RACK	4C
O																	#22"	ESPRIGAS	PER MFG	CO2 TANK	4D
O																		CO2Meter.com	RAD-0102-6	CO2 MONITOR & DISPLAY	4D-S1
O				FS	1/2"												34"x17"x6 1/2"	KEC	CUSTOM	36" COLD PAN	5C
O																	SEE PLAN	KEC	CUSTOM	S/S COUNTER WITH SINK	6B
O										REF. ELEC.							SEE PLAN	KEC	CUSTOM	MOBILE HOT WELLS COUNTER - DT	6M
O																	SEE PLAN	KEC	CUSTOM	S/S COUNTER - DT	8J
O										24"							SEE PLAN	KEC	CUSTOM	CASHIER & BEVERAGE COUNTER- DT	9B
O										24"	C	14.8A	1		120	NEMA 5 PLUG	11" X 22" X 34"	BUNN	TB3	ICED TEA BREWER (2)	9D
O				FS	1/2"	24"	1/2"			84"	C	1.1A	1		120	---	22" X 14" X 26.5"	MANITOWOC	**IB-0894YC**	800 LBS. ICE MACHINE	10J
O										16"	D	11.8A	1		208/230	ON ROOF	34"X 24.13"X 25.75"	MANITOWOC	**CVD-0675**	REMOTE CONDENSER	10J-S1
O													1		**115**	**FREE STANDING**	**34" X 22" X 44"**	**MANITOWOC**	**IY0620A**	CUBER HALF DICE CUBE	10L
O													1		**---**	**ABOVE ICE MACHINE**	**24"X 17.5"X 21.5"**	**MANITOWOC**	**D420**	STORAGE BIN	10L-S1
																				KITCHEN EQUIPMENT	
O	450	10"	1-1/2"	FS	2"	10"	1/2"									SEE DETAIL	93"x42"	KEC	CUSTOM	93" CHINESE RANGE (L)	20A
O	190	10"	1"	FS	2"	10"	1/2"									SEE DETAIL	42"x42"	KEC	CUSTOM	42" CHINESE RANGE	20Q
O	190	10"	1"	FS	2"	10"	1/2"			18"	C	7A	1		120	SEE DETAIL	42"x42"	KEC	CUSTOM	42" CHINESE RANGE	20R
O	122 EA	14"	1 1/2"							24"	C	-	1		120		47"x31-1/2"x51-5/8"	FRYMASTER	MJ45-FPP345C	FRYER	21B
O	54	10"	3/4"												120		24"X31.5"X15.25"	VULCAN	MSA24-C0100P	24" GAS GRIDDLE	23E
GRILL MEMA PLUG/CONNECTOR (1)										36"	C	17.3A	1		208		10.4"X22.9"	VULCAN	VMCS-101	(2) ELECTRIC GRIDDLE TOP	
O										24"	C	14.8A	1		120	NEMA 5	19.9"X34.5"X41.3"	WINSTON	HA4005	RICE HOLDING CABINET	24H
O	34.6	10" & 32"	3/4"														24"x19"x17"	PANTIN	GC-6100(N)	RICE COOKER	25A
O										24"	C	9A	1	1/2	115	NEMA 5-15P	60"X33"X36"	RANDELL	9205F-290	60" WORKTOP FREEZER	30L
O				FS	3/4"					130"	D (2)	2.0AMPS	1	1.5	208		SEE PLAN	**KEC**	CUSTOM	WALK-IN COOLER UNIT	31
O											D (2)	35.0A	1	1.5	208		SEE PLAN	**KEC**	CUSTOM	WALK-IN COOLER COND.	31-S
O				FS	3/4"					130"	D (2)	FREEZER FAN COIL UNIT POWERED FROM CONDENSER UNIT					SEE PLAN	**KEC**	CUSTOM	WALK-IN FREEZER	32
O											D (2)	30.0A	1	1.5	208		SEE PLAN	**KEC**	CUSTOM	WALK-IN FREEZER COND.	32-S1
O											D/ID	500W	1		120		SEE PLAN	**KEC**	CUSTOM	W.I.F. LTG, DOOR HEATER	32-S7
O										24"	C	15A	1	1/2	120	SELF CONTAINED	84"x33"x35"	RANDELL	9050K-7MPR2-NSB	84" REF. PREP. TABLE	34O
O										24"	C	9A	1	1/3	120	SELF CONTAINED	48"x33"x35"	RANDELL	9030K-7	48" REF. PREP. TABLE	34D
O				FS	2"	14"	3/4"	14"	3/4"								100"X30"	KEC	CUSTOM-(PS-100L)	POT SINK	40A
O				FS						88"	C	1.52 KW	1	2	208		28"x33"x82"	ELECTROLUX	727655	THAWING CABINET	40T
O				FS	2"	14"	3/4"	14"	3/4"							1 COMPARTMENT	42"x30"	KEC	CUSTOM-(VS-42)	42" VEGETABLE SINK (R)	41B
O				FS	2"	14"	3/4"	14"	3/4"							1 COMPARTMENT	42"x30"	KEC	CUSTOM-(VS-42)	42" VEGETABLE SINK (L)	41C
O										18GA POLISHED (WALL MTD. @ 59" A.F.F.)							SEE PLAN	**PANDA WAREHOUSE**	CUSTOM (NSF)	12"D S.S. WALL MTD. SHELF	43A
O										18GA POLISHED (WALL MTD. @ 71" A.F.F.)							SEE PLAN	**PANDA WAREHOUSE**	CUSTOM (NSF)	18"D S.S. WALL MTD. SHELF	43B
O										4 SHELVES MTD. @ 8" A.F.F., 26" A.F.F., 54" A.F.F., 72" A.F.F.							SEE PLAN	GOLD BOND	ISS	18"D WIRE SHELVES	44A
O										UNDER CABINET SHELVES WITH CASTER MTD. @ 8" A.F.F., 20" A.F.F.							SEE PLAN	GOLD BOND	ISS	SHORT 18"D WIRE SHELVES	44A-U
O										4 SHELVES MTD. @ 36" A.F.F., 48" A.F.F., 60" A.F.F., 72" A.F.F.							SEE PLAN	GOLD BOND	ISS	24"D WIRE SHELVES	44C
O										UNDER CABINET SHELVES MTD. @ 8" A.F.F., 14" A.F.F.							SEE PLAN	GOLD BOND	ISS	SHORT 24"D WIRE SHELVES	44C-U
O																	24"x 30" x 24"	KEC	CUSTOM	S.S. RICE COOKER STAND	46A
O																	22"x 20" x 34.06"	KEC	CUSTOM	RICE WARMER STAND	46B
O																	24"x 33" x 28"	KEC	CUSTOM	S.S. GRILL STAND	46H
O										50"	C	10A	1	1	120	9 15/16"x19-11/16"x19-3/4"	ELECTROLUX	DITO-TRS24	FOOD PROCESSOR	53
O				FS	7/8"	20"	3/4"	20"	3/4"	18"	C	53A	1	4	208	DISCONNECT @ 90°	32"x37"x88"	HOBART	PW10SER	POTWASHER	70D
O				FS													14"x14"x21"	HOBART	WS-40	WATER SOFTENER	70D1
																				SMALL EQUIPMENT	
O				2"		24"	1/2"	24"	1/2"							W/TOWEL & SOAP	14 1/4"x18 1/2"	GSW	HS-1615NPASS	HAND SINK	45A
O										24"	C	105W	1		120	ON S.S. COUNTER	17" Ø	WELBON	WRS-1088BS	RICE WARMER	54A
O										84"	DC	1800W	1		208	PLUG: NEMA 6-15R	17 1/2"x13 5/8"x22 9/16"	SHARP	R-CD1800M	MICROWAVE	55A
BY G.C.																AS REQUIRED BY LOCAL FIRE DEPT., CHECK LOCATION WITH PROJECT MANAGER				FIRE EXTINGUISHER	56
O																	SEE DETAIL	SAN-JAMAR	SANJT7500TBK	PAPER TOWEL DISPENSER	60D
O																WALL MOUNT	12"x20"x77"	GSW	5-DOOR	LOCKER (2)	61B
O																	20"X20"X23"	**TIDEL**	**CUSTOM**	SMART SAFE	62B
																				POS EQUIPMENT	
O																SEE ELEV. ON E-200	48" X 28" X 42"	KEC	CUSTOM	MANAGER STATION	49A
O										REF ELEV	C	100W	1		120	SEE DETAIL		**DELL OPTIPLEX**	**Xe2**	COMPUTER	83A
O										REF ELEV	C	50W	1		120	SEE PLAN		**BROTHER**	**MFC-LC2700DW**	POS PRINTERS	86A
O										REF ELEV	C	50W	1		120			**BROTHER**	**MFC-LC2700DW**	FAX	87
O										REF ELEV	C	500W	1		120	CUSTOM	11 1/4"x14 1/2"x9"	RESNOS	S 460	CASH REGISTER SYSTEM	94
																				MEP EQUIPMENT	
O																SEE MECH. DWG.	SEE PLAN	CAPTIVE AIR	CUSTOM	EXHAUST HOOD	M1
O																SEE MECH. DWG.	SEE PLAN	CAPTIVE AIR	CUSTOM	HOOD CONTROL PANEL	M4
O																SEE MECH. DWG	SEE PLAN	CAPTIVE AIR		FIRE SUPPRESSION SYSTEM	M5
BY G.C.																SEE MECH/ELEC DWG	SEE PLAN			RECESSED ANSUL PULL BOX	M6
O										90"	D	5.1A	1	1/2	115	SEE MECH/ELEC DWG	42" X 10 5/8"	MARS	STD242-1U	BACK DOOR AIR CURTAIN	M8a
BY G.C.										24"	D	20A	1		120	SEE ELEC. DWG	25"X 9" X 10 3/8"	QUIK-SERV	CF-25 NON-HEATED	DT WINDOW AIR CURTAIN REGIONAL APPLICATION EITHER OR, NOT BOTH	M9a
BY G.C.										24"	D	30A	1		120 & 208	SEE ELEC. DWG	25"X 9" X 14 3/8"	QUIK-SERV	CHF-25 HEATED		
BY G.C.										24"	D	20A	1		120	SEE ELEC. DWG	47.5"X 59.5"	QUIK-SERV	SST-4860E	DT WINDOW	M10
O																SEE PLUMBING DWG	26.88" X 25.14" X 90.56"	MARENGO FABRICATED	600058 ASSEMBLY	GREASE TANK	P-OT1
BY G.C.				3"	36"	–	36"	–			D					FLOOR TYPE	24" X 24" X 13"	G.S.W. PHONE:1800-897-5999	SE2424FM	STAINLESS STEEL MOP SINK	P1
BY G.C.	398	100"								84"	C	8A	1		120	SEE PLUMBING DWG	39" X 29.75" X 13"	RINNAI	MTO-00247	GAS TANKLESS WATER HEATER	P3 (2)
O					96"	1/2"										WALL MOUNT	8"x2 3/8"x23 5/8"	3M WATER FILTRATION	BEV190-56164-01	WATER FILTER	P4
O																WALL MOUNT	10"x8 5/8"x18 1/2"	WATTS	OFTWH-C	WATER FILTER	P5
O										REF ELEV	C	50W	1		120	SEE ELEV. ON E-200	SEE PLAN	HYPERACTIVE		HYPERACTIVE TIMER SYS.	94-1A
O										48"	C	50W	1		120	SEE PLAN	15" X 13"	DELL (17" COLOR)		LCD MONITOR-MANAGER	94-2-16
O										REF ELEV	C	50W	1		120	SEE ELEV. ON E-200	SEE PLAN	HME		HME INTERCOM SYS.	94-3-1
O										REF ELEV	C	60W	1		120	SEE PLAN	15"	POSIFLEX	KS7215	LCD DT MONITOR	94-W
O										REF ELEV	C	50W	1		120	W/ EMI LOCK	SEE PLAN	TOSHIBA (TIME LAPSE)		SECURITY VCR	95-4-S2
O										98"	C	50W	1		120	SEE ELEC. DWG	15" X 13"	DELL (17" COLOR)		SECURITY MONITORS	95-4-S3
O										REF ELEV	C	100W	1		120	IN S.S. COUNTER	SEE PLAN			MUSIC EQUIPMENT	95-5
BY G.C.																SEE ELEC. DWG				ELECTRICAL PANEL	E7
																				SIGNAGE	
O																	REF. INT. ELEV'S	LSI	CUSTOM	MENU BOARD	D2b
O																BF-POWER COAT "DF125 SILVER"		FAD	–	COMMUNITY BOARD	CB-H
O										REF ELEV	C	130W	1		120	DEDICATED CIRCUIT	48.9" X 28.1" X 1.3"	LG	55WS50BS-B	LCD DISPLAY MONITOR	96-3B

PANDA EXPRESS, INC.
1683 Walnut Grove Ave.
Rosemead, California
91770
Telephone: 626.799.9898
Facsimile: 626.372.8288

All ideas, designs, arrangement and plans indicated or represented by this drawing are the property of Panda Express Inc. and were created for use on this specific project. None of these ideas, designs, arrangements or plans may be used by or disclosed to any person, firm, or corporation without the written permission of Panda Express Inc.

REVISIONS:

ISSUE DATE:
ISSUE FOR PERMIT 10-20-22
ISSUE FOR BID 01-30-23

DRAWN BY: AE/SS

PANDA PROJECT #: D23503
PANDA STORE #: -
ARCH PROJECT #: 261-443

MPW
MPW ENGINEERING, LLC
110 W. 7TH STREET • SUITE 600 • TULSA, OK 74119
(918) 582-4088 • (918) 582-4087 FAX

CHARLES L. MADDIX — REGISTERED ENGINEER — AGRICULTURE — 112011 — STATE OF TENNESSEE — 01/26/2023

PANDA EXPRESS
PANDA HOME 2600
NORTH RIVERSIDE DR & 2ND ST.
CLARKSVILLE, TN 37040

E-001
ELECTRICAL SCHEDULES

ISSUE FOR BID 01-30-23

ISSUE FOR BID 01-30-23